

Tender Inviting Authority: SOE&M,GM Unit Kuju

Name of the Work / Contract No:	Construction and installation of 3 no of shed of size 3M X 2M X 5M to be installed at filter plant (1no.) for pump starter and at quarry no.1 (2 no.) for 2000GPM pump starter and switch along with erection of 4 no. earhpit for body grounding of starter,switch and motor of pundi Project Under Kuju Area.	NIT No. : GM (K)/EnM/e-Tender/25-26/96					
Category of Services ( To Be Selected by Department)		Category of Bidder ( To Be Selected by Bidder)	To Be Entered by Department				
ITC Available	Works Contract	Bidder's Status (Mandatory)	Rate of GST (in %)	Total GST(in Rs.)	GST to be Paid By Bidder (in Rs.)	GST to be Paid By CIL/Subsidiary (in Rs.)	
Name of the Bidder/ Bidding Firm / Company :		Select	18	0.00	0.00	0.00	

PRICE SCHEDULE  
(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only )

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate in Rs. P	BASIC RATE In Figures To be entered by the Bidder in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	7	8
2	Earthing with copper earth plate 600mm X 600mm X 3MM thick including accessories, and providing masonry enclosure with cover plate having locking arrangement and watering pipe of 2.7metre long etc with charcoal/coke and salt as required 1No.for 30HP pump motor body grounding,1no for starter body grounding and 2 no. for 2000GPM pump starter and switch body grounding	4.00	nos			0.00	INR Zero Only
3	Supply and installation of 1100V Grade, single core, XLPE unarmoured, aluminum cable, 35sq.mm. for earthing connection	40.00	M			0.00	INR Zero Only
4	Supply and fixing crimping type alum lugs as per I.S.S specification suitable for following size of cable with alu/copper solid/stranded conductor evenly crimped with high pressure tool and conneted to switch gear/bus/M.C.C.B./M.C.B.etc required complete 35sq.mm size for Earthing connection	8.00	nos			0.00	INR Zero Only
5	Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m inwidth as well as 10 sqm on plan) including disposal of excavated earth, lead upto 1.5 m, disposed earth to be levelled and neatly dressed. 2.8.1 Ordinary rock. For base 1 Mtrs x 1 Mtrs x 1 Mtrs x 4 x 3 shed= 12 Cu.Mtrs	12.00	M3			0.00	INR Zero Only
6	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level: 1:2:4 (1 cement: 2 coarse sand (zone-III): 4 graded stone aggregate 20 mm nominal size). For shed - 1M x 0.3M x 0.3M x 4 x 3 shed= 1.08 Cu. Mtr., for starter base at filter plant -3 Mtrs x 0.12 Mtr x 2 Mtr = 0.72 Cu.Mtrs.	1.80	M3			0.00	INR Zero Only
7	Centering and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns, etc. for mass concrete	7.08	M2			0.00	INR Zero Only
8	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, Including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete. 395.24 <sup>3</sup> * 3 = 1024.56	1185.70	KG			0.00	INR Zero Only
9	Providing and fixing 0.63 mm thick with zinc coating not less than 275gm / (m <sup>2</sup> * 2) corrugated G.S. sheet roofing including vertical / curved surface fixed with polymer coated J or L hooks, bolts and nuts 8 mm diameter with bitumen and G.I. limpet washers or with G.I. limpet washers filled with white lead, including a coat of approved steel primer and two coats of approved paint on overlapping of sheets complete (up to any pitch in horizontal/ vertical or curved surfaces), excluding the cost of purlins, rafters and trusses and including cutting to size and shape. For shed top cover - 3M * 2M + for * 3 side cover from top - (4M * 2M * 2 + 4M * 3M) + For front gate -4M * 3M =46 Sq.M.	46.00	M2			0.00	INR Zero Only
10	Total Impact of GST for the purpose of CTC	1.000	nos		0.00	0.00	INR Zero Only
Total in Figures						0.00	INR Zero Only
Quoted Rate in Words		INR Zero Only					